




**Environmental Waste
Management Associates**

SDMS Document



128259

Corporate Headquarters:
100 Misty Lane
P.O. Box 5430
Parsippany, NJ 07054
phone (973) 560-1400
fax (973) 560-0400
website - www.ewma.com

Via FedEx Priority Overnight

August 18, 2004

Mr. Stephen Kehayes, Case Manager
NJDEP- Office of Brownfields Reuse
P. O. Box 028
401 East State Street
Trenton NJ 08625-0028

Re: Gypsum Landfill Remedial Investigation and Existing Cap Thickness Delineation Report
Former Celotex Industrial Park Property
525 River Road, Edgewater, Bergen County, NJ
EWMA Project #: 202334

Dear Mr. Kehayes:

Environmental Waste Management Associates, LLC (EWMA), on behalf of Edgewater Enterprises, has completed the proposed additional remedial investigation and existing cap thickness delineation for the Gypsum Landfill area at the referenced site. This letter report summarizes the results of these additional investigation activities.

Background

EWMA's initial proposal for the additional investigation activities was outlined in the Remedial Investigation Report/ Remedial Investigation Workplan (RIR/RIW) dated March 20, 2002. On February 26, 2003, NJDEP issued a comment letter outlining additional requirements, summarized as follows:

- Expansion of the areas shown as containing less than 18-inches of cover material to include grids where no delineation soil boring was installed (Figure 4); and,
- Additional lateral delineation of PCBs to the north, northwest, and northeast of the former sample location LFTP-4 (13'-13.5').

On August 25, 2003, EWMA submitted a response to the NJDEP comment letter dated February 26, 2003. Specifically, the following was proposed to satisfy additional NJDEP requirements:

- Grids where no soil borings were drilled to establish cap thickness, were included in the areas having less than 18 inches of cover (Figure 4);
- A total of thirty-five (35) additional soil borings were proposed to further delineate the cap thickness, especially in the grids where no soil borings were previously installed;
- Three (3) additional lateral PCB delineation soil borings were proposed in the vicinity of LFTP-4 per NJDEP requirements.

Mr. Stephen Kehayes

Gypsum Landfill Remedial Investigation and Existing Cap Thickness Delineation Report

Former Celotex Industrial Park Property

525 River Road, Edgewater, Bergen County, NJ

EWMA Project #: 202334

Page 2

On December 22, 2003, NJDEP issued a response letter that included a response to EWMA's submittal dated August 25, 2003 for the Gypsum Landfill area. The NJDEP response letter approved the proposed additional investigation activities. In addition, NJDEP outlined the following revisions to the cap thickness requirement:

- For the landscaped areas and areas with soil cover, a cap thickness of 18 inches or above was required;
- For areas utilizing asphalt, paving blocks, or brick/stone, a cap thickness of 12 inches was acceptable.

The above revisions were acknowledged by Wolff & Samson, on behalf of Edgewater Enterprises, in their letter to NJDEP dated January 13, 2004.

PCB/ Metals Delineation Investigation

A number of proposed additional soil borings were installed within the Gypsum Landfill area for vertical and lateral delineation of PCB, arsenic, and lead compounds detected at former sample locations. EWMA was unable to conduct lateral and vertical delineation soil borings (LFSS-4-WD and LFSS-4-V) related to the former sample location LFSS-4 due to unfavorable access conditions. Specifically, this sample location was at the bottom of the existing drainage ditch, with steep embankment slopes prohibiting the placement of a drill rig to conduct the soil borings in a safe manner. The boring locations are depicted on on the revised Figure 5.

All soil sampling was conducted in accordance with NJDEP's *Field Sampling Procedures Manual (FSPM)*, May 1992. All soil samples were analyzed by Integrated Analytical Laboratories, LLC (IAL) of Randolph, NJ (NJDEP Certification # 14751).

A summary of the additional delineation soil samples collected is summarized in the attached Table 1, and the location of the soil borings is shown in the attached revised Figure 5. The results of the delineation soil samples are summarized in Table 2. Soil boring logs for all sample locations are provided in Appendix 1. The laboratory analytical data package (IAL Case # 03710) and the Electronic Data Deliverable (EDD) packages for the soil samples are attached as Appendix 2, and Appendix 3, respectively.

The results of PCB analysis of the additional delineation soil samples did not detect the presence of PCB compounds in any of the soil samples, except for LFTP-4-ND (13'-13.5') where Aroclor-1254 PCB compound was detected at 0.573 mg/kg, slightly above the NJDEP Residential Direct Contact Soil Cleanup Criteria (RDCSCC) of 0.49 mg/kg, but below the NJDEP Non-Residential Direct Contact Soil Cleanup Criteria (NRDCSCC) of 2.0 mg/kg.

The results of proposed metals analysis of the additional delineation soil samples indicated the presence of arsenic at 74.5 mg/kg at LFHD-1 (25'-26') and 243 mg/kg at LFHD-3 (25'-26'), above the NJDEP NRDCSCC of 20 mg/kg.

The isolated PCB concentrations detected are below the NJDEP NRDCSCC, and can be adequately addressed through the existing engineering controls and the placement of the proposed institutional



Mr. Stephen Kehayes

Gypsum Landfill Remedial Investigation and Existing Cap Thickness Delineation Report

Former Celotex Industrial Park Property

525 River Road, Edgewater, Bergen County, NJ

EWMA Project #: 202334

Page 3

criteria, and can be adequately addressed through the existing engineering and proposed institutional controls.

The additional proposed delineation sampling in the vicinity of LFSS-4 was not completed due to unfavorable and unsafe access conditions. Based on the results of PCB, arsenic, and lead analysis for the remaining delineation soil samples summarized above, EWMA requests that the delineation sampling for the former location LFSS-4 be waived.

Landfill Cap Thickness Delineation

In addition to the proposed thirty-five (35) soil borings, thirty-five (35) more soil borings (i.e. a total of 70 soil borings) were installed to address the data gaps in the landfill cap sampling grid. Some of these borings were installed to re-evaluate grids where borings were previously installed during the December 2001-January 2002 landfill cap thickness investigation. A review of the previous investigation method revealed that the procedure used for the cap thickness evaluation may not have been most accurate. The previous borings were installed using an auger which allows visual inspection of the soil in the ground, thereby makes it difficult to evaluate the soil column as a whole and accurately determine the gypsum depth. In addition, mixing of the strata in the drill cuttings may have occurred which would also make gypsum depth evaluation difficult.

On June 7 and June 22, 2004 a total of seventy (70) borings were installed in the Gypsum Landfill area by Summit Drilling (Summit) under the supervision of EWMA. For activities conducted on June 7, 2004, a Geoprobe drill rig was used on June 7, 2004 to install borings in the asphalt and brick/stone paved areas. On June 22, 2004, a jack hammer modified to drive standard split spoons was used to install borings on the slopes of the water quality basin and in landscaped areas not accessible with the Geoprobe.

Less than 18 inches of material was recovered in three (3) borings installed in grids A'12, B5, and H10 which are located in the water quality basin and landscaped areas. The soil cores for all seventy (70) locations were photographed and soil boring logs with the corresponding photos are attached in Appendix 4. The boring locations and variations in the cap thickness are depicted on the Existing Cap Thickness Plan attached as Figure 2. The cap thickness data from the current and previous investigations are summarized by grid location on Table 3.

A review of the Existing Cap Thickness Plan (Figure 2) indicates that with the exception of six (6) isolated locations (within grids A'12, G10, H10, I3, I5, and J5) out of the seventy (70) locations, the additional soil borings showed that the fill thickness meets and/or exceeds the NJDEP requirement. The inclusion of asphalt, brick/stone thickness will further reduce the locations and limited areas with total cap thickness below the NJDEP requirement. However, EWMA believes that the engineering controls currently present and maintained at the site provide adequate protection against direct contact with the underlying gypsum landfill material, erosion, and/or migration of any soil particles or cover material. Therefore, EWMA requests that no further investigation or disruption of the existing controls be required in the Gypsum Landfill area.

Mr. Stephen Kehayes

Gypsum Landfill Remedial Investigation and Existing Cap Thickness Delineation Report

Former Celotex Industrial Park Property

525 River Road, Edgewater, Bergen County, NJ

EWMA Project #: 202334

Page 4

Landfill Cap Repair

During EWMA's recent activities a few small areas of settlement were observed in and adjacent to the water quality basin area of the gypsum landfill cap. On July 16, 2004, Art Semeraro Construction Company repaired these areas by filling them to the required cap thickness with clean soil and rip rap. Approximately 6 cubic yards of top soil and 8 cubic yards of rip-rap were used for the repairs and grass seed was planted on the top soil areas. The repaired areas are depicted on Figure 2.

Conclusions & Recommendations


Based on the results of the investigation activities presented above, EWMA provides the following conclusions and recommendations:

- PCB, lead, and arsenic contamination has been adequately investigated and delineated within the Gypsum Landfill area, and that no further investigation activities are necessary due to the presence of adequate engineering controls and proposed institutional controls;
- The results of the additional cap thickness investigation and delineation indicate that with the exception of six (6) isolated locations out of the seventy (70) locations, the additional soil borings showed that the fill thickness meets and/or exceeds the NJDEP requirement throughout this area. The engineering controls currently present and maintained at the site provide adequate protection against direct contact with the underlying gypsum landfill material, erosion, and/or migration of any soil particles or cover material;
- EWMA believes that all pending remedial investigation and/or cap thickness evaluation/ remediation requirements have been adequately addressed and that no further investigation or remedial action is necessary.

Should you have any questions or require additional information to complete your review, please do not hesitate to call me or Paul Schatz at (973) 560-1400 ext. 155 or 151, respectively.

Sincerely,

Environmental Waste Management Associates, LLC




Ajay Kathuria, P.E.

Senior Project Engineer

Attachments

cc: Richard LaBarbiera, P.E., Edgewater Enterprises
 Richard Ho, EPA – Region 2
 Dennis Toft, Wolff & Samson
 Daniel A. Nachman, Dan Raviv Associates, Inc. (DRAI)
 Kevin D. Orabone, EWMA
 Paul V. Schatz, C.P.G., EWMA




SCALE: AS SHOWN PROJECT #
DATE: 3/20/02 202334

DRAWN BY: RR
CHECKED BY: PB
FILE: k:\drawings\edgewater\Opportunities\202334.dwg

EWMA

FIGURE #
2



TABLES

TABLE 1
ADDITIONAL DELINEATION SAMPLING PLAN
FORMER CELOTEX INDUSTRIAL PARK PROPERTY
RIVER ROAD, EDGEWATER, NEW JERSEY

GYPSUM LANDFILL AREA

Designation	Medium	Sample Depth	Analytical Parameters	Comments
LFTP-3-V	Soil	28-30'	PCB	Vertical Delineation of LFB3
LFTP-4-V	Soil	25-26'	PCB	Vertical Delineation of LFTP-4
LFTP-4-ND	Soil	13-13.5'	PCB	Lateral Delineation of LFTP-4 at Sample Depth
LFTP-4-WD	Soil	13-13.5'	PCB	Lateral Delineation of LFTP-4 at Sample Depth
LFTP-4-ED	Soil	13-13.5'	PCB	Lateral Delineation of LFTP-4 at Sample Depth
LFSS-4-V*	Soil	25-26'	PCB, As, Pb	Vertical Delineation of LFSS-4 Horizontal Delineation of LFB3 in a Western Direction Define Limits of As and Pb in West Direction
LFSS-4-WD*	Soil	0-2'	PCB	Horizontal Delineation of LFSS-4 in a Western Direction
LFHD-01	Soil	25-26'	PCB, As, Pb	Horizontal Delineation of LFB3 in North Direction Define Limits of As and Pb in North Direction
LFHD-02	Soil	25-26'	PCB, As, Pb	Horizontal Delineation of LFB3 in East Direction Define Limits of As and Pb in East Direction
LFHD-03	Soil	25-26'	PCB, As, Pb	Horizontal Delineation of LFB3 in South Direction Define Limits of As and Pb in South Direction

* Soil borings not installed due to unfavorable access

ENVIRONMENTAL WASTE MANAGEMENT ASSOCIATES, LLC.

Table 2: Soil Sample Analytical Results Summary Table

Project: Edgewater Enterprises - Gypsum Landfill Area

Project Number: 202334

Site: Former Celotex, 225 River Road, Edgewater, NJ

Client ID: Sample Depth: Lab ID: Date Sampled: Matrix:	NJDEP	NJDEP	NJDEP	LFTP-4-ED			LFTP-4-ND			LFTP-4-WD			LFTP-4-V		
	RDC	NRDC	IGW	13'-13.5'			13'-13.5'			13'-13.5'			25'-26'		
	SCC	SCC	SCC	03710-001			03710-002			03710-003			03710-004		
	04/26/2004			04/26/2004			04/26/2004			04/26/2004			04/26/2004		
				Soil			Soil			Soil			Soil		
PCB's (ppm)				Conc	Q	MDL	Conc	Q	MDL	Conc	Q	MDL	Conc	Q	MDL
Aroclor-1016	0.49	2	50	ND	0.018	ND	0.017	ND	0.023	ND	ND	0.020			
Aroclor-1221	0.49	2	50	ND	0.018	ND	0.017	ND	0.023	ND	ND	0.020			
Aroclor-1232	0.49	2	50	ND	0.018	ND	0.017	ND	0.023	ND	ND	0.020			
Aroclor-1242	0.49	2	50	ND	0.018	ND	0.017	ND	0.023	ND	ND	0.020			
Aroclor-1248	0.49	2	50	ND	0.018	ND	0.017	ND	0.023	ND	ND	0.020			
Aroclor-1254	0.49	2	50	ND	0.018	<u>0.573</u>	0.017	ND	0.023	ND	ND	0.020			
Aroclor-1260	0.49	2	50	ND	0.018	ND	0.017	ND	0.023	ND	ND	0.020			
Total PCB	0.49	2	50	ND	0.018	<u>0.573</u>	0.017	ND	0.023	ND	ND	0.020			
Metals (ppm)															
Arsenic	20	20	NA	~	~	~	~	~	~	~	~	~			
Lead	400	600	NA	~	~	~	~	~	~	~	~	~			

3.14 = Results above the NJDEP Residential Direct Contact Soil Cleanup Criteria

3.14 = Results above the NJDEP Non-Residential Direct Contact Cleanup Criteria

3.14 =Results above the NJDEP Impact to Ground Water Soil Cleanup Criteria

~ = Sample not analyzed for

ND = Analyzed for but Not Detected at the MDL

J = The concentration was detected at a value below the MDL

All qualifiers on individual Semivolatiles are carried down through summation.

ENVIRONMENTAL WASTE MANAGEMENT ASSOCIATES, LLC.

Table 2: Soil Sample Analytical Results Summary Table

Project: Edgewater Enterprises - Gypsum Landfill Area

Project Number: 202334

Site: Former Celotex, 225 River Road, Edgewater, NJ

Client ID:	NJDEP	NJDEP	NJDEP	LFTP-3-V			LFHD-1			LFHD-2			LFHD-3		
	Sample Depth:	RDC	NRDC	IGW	27'-29'		25'-26'		25'-26'		25'-26'		25'-26'		25'-26'
Lab ID:	SCC	SCC	SCC	03710-005			03710-006			03710-007			03710-008		
Date Sampled:	04/27/2004			04/27/2004			04/27/2004			04/27/2004			04/27/2004		
Matrix:				Soil			Soil			Soil			Soil		
PCB's (ppm)				Conc	Q	MDL	Conc	Q	MDL	Conc	Q	MDL	Conc	Q	MDL
Aroclor-1016	0.49	2	50	ND	0.023	ND	0.024	ND	0.023	ND	0.023	ND	0.023	ND	0.023
Aroclor-1221	0.49	2	50	ND	0.023	ND	0.024	ND	0.023	ND	0.023	ND	0.023	ND	0.023
Aroclor-1232	0.49	2	50	ND	0.023	ND	0.024	ND	0.023	ND	0.023	ND	0.023	ND	0.023
Aroclor-1242	0.49	2	50	ND	0.023	ND	0.024	ND	0.023	ND	0.023	ND	0.023	ND	0.023
Aroclor-1248	0.49	2	50	ND	0.023	ND	0.024	ND	0.023	ND	0.023	ND	0.023	ND	0.023
Aroclor-1254	0.49	2	50	ND	0.023	ND	0.024	ND	0.023	ND	0.023	ND	0.023	ND	0.023
Aroclor-1260	0.49	2	50	ND	0.023	ND	0.024	ND	0.023	ND	0.023	ND	0.023	ND	0.023
Total PCB	0.49	2	50	ND	0.023	ND	0.024	ND	0.023	ND	0.023	ND	0.023	ND	0.023
Metals (ppm)															
Arsenic	20	20	NA	~	~	<u>74.5</u>	1.58	15.3	1.54	<u>243</u>	1.60				
Lead	400	600	NA	~	~	198	0.792	18.5	0.771	268	0.799				

3.14 = Results above the NJDEP Residential Direct Contact Soil Cleanup

3.14 = Results above the NJDEP Non-Residential Direct Contact Clea

3.14 =Results above the NJDEP Impact to Ground Water Soil Cleanup

~ = Sample not analyzed for

ND = Analyzed for but Not Detected at the MDL

J = The concentration was detected at a value below the MDL

All qualifiers on individual Semivolatiles are carried down through summation

TABLE 3
GYPSUM CAP INVESTIGATION SUMMARY
FORMER CELOTEX INDUSTRIAL PARK
225 RIVER ROAD, EDGEWATER, NEW JERSEY

	A'	A'	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P
15		>/=18	>/=18	>/=18	>/=18	>/=18	12	13	14.5	8	>/=18	3	7	x	x	x	x
14		>/=18	>/=18	>/=18	>/=18	>/=18	>/=18	>/=18	6	>/=12	8	>/=12	3.5	>/=12	x	3	>/=18
13	>/=18	>/=18	>/=18	13	>/=18	>/=18	>/=18	>/=18	>/=18	>/=12	>/=18	>/=18	>/=18	>/=18	x	5	1
12	R<18	>/=18	>/=18	10.5	>/=18	x	x	x	x	x	x	x	x	x	x	x	x
11	>/= 18	>/=18	>/=18	>/=18	>/=18	>/=18	>/=18	13	>/=12	>/=12	>/=18	>/=18	>/=18	12	>/=18	>/=18	3
10	>/= 18	>/= 18	15	x	>/=18	>/=18	>/=18	10	10	>/=12	>/=18	12	13	>/=18	x	11	>/=18
9		>/= 18	x	>/=18	>/=18	>/=18	>/=12	>/=12	>/=12	>/=18	10	>/=18	>/=18	13	x	>/=18	3
8		8	15	>/=18	x	>/=18	>/=18	>/=18	>/=18	14	>/=18	>/=18	x	>/=18	x	6.5	9
7		13	>/= 18	>/=18	>/=18	x	>/=18	>/=18	>/=18	>/=18	x	x	>/=18	>/=18	x	9	>/=18
6		>/=18	>/= 18	x	x	>/=18	>/=18	>/=18	>/=18	>/=18	x	>/=18	>/=18	>/=18	6	x	9
5		>/=18	R<18	>/=18	>/=18	x	x	15	15	16	15	>/=18	>/=18	13	>/=18	9	x
4		>/=18	>/=18	x	x	>/=18	16	16	>/=18	13	>/=18	>/=18	>/=18	7	11	x	15
3		>/=18	12	16	x	>/=18	>/=18	>/=18	9	10	9	9	14	x	x	x	x
2		>/=18	>/=18	16	>/=18	>/=18	14	13	x	x	x	x	x	x	x	x	x
1		17	>/=18	15	>/=18	17	x	x	x	x	x	x	x	x	x	x	x

Note:

Numbers in Bold are less than 18" cover

X - Grid Was not sampled

- >/= 18 Grids where 18 inches or more cover material was established during previous investigation
- >/= 18 Grids where no boring was installed during previous investigation, but recent investigation shows 18 inches or more of cover material
- >/= 18 Grids where 18 inches or more of cover material was observed during previous as well as recent investigation
- >/= 18 Grids where previous investigation showed less than 18 inches of cover material, but recent investigation showed 18 inches or more of cover material
- R<18 Grids where no boring was installed during previous investigation and less than 18 inches was recovered in spoon or geoprobe macrocore during recent investigation
- >/=12 Grids where no boring was installed during previous investigation, but recent investigation shows 12 inches or more of cover material
- >/= 12 Grids where 12 inches or more of cover material was observed during previous as well as recent investigation
- >/= 12 Grids where previous investigation showed less than 12 inches of cover material, but recent investigation showed 12 inches or more of cover material



**Environmental Waste
Management Associates, LLC**

EWMA Job #:
202334
Boring #:
LFTP-4-ED
Install Date:
4/26/04

Site Name: Former Celetex Property

Site Location: Edgewater, NJ

Completion Date: 4/26/04

Geologist: Joe Kruik

Driller: Steve Yotkovski/Bonnie Crespo Drill Rig: GP1100CXB


Bit: Tricone Hammer Wt: 110' Drop: 30" Total Depth: 14'

Sampler Type: 2" diameter SS Split Spoon C.W. Encountered: 12'

Sampler Type: 2 diameter SS Split Spoon G.W. Encountered: 12
G.W. Stabilized: 12

G.W. Stabilized: 12

BORING LOCATION SKETCH (N.T.S.)



SOIL/GEOLOGICAL DESCRIPTION						
DEPTH (FT.)	SAMPLE ID AND DEPTH	PID/FID/QUA (METER UNITS)	BLOWS/16.0"	RECOVERY (INCHES)	SOIL TYPE	DEPTH (FT.)
1	LFTP 4-ED	0.0	20	CL	Fill	0-2' Asphalt, Road Stone
2						2
3						3
4						4
5						5
6						6
7						7
8						8
9						9
10						10
11						11
12						12
13						13
14						14
15						15
16						16
17						17
18						18
19						19
20						20
21						21
22						22
23						23
24						24



**Environmental Waste
Management Associates, LLC**
PO Box 5430, Parsippany, NJ, 07054
Phone: (973) 560-1400 Fax:(973) 560-0400

EWMA Job #:
202334
Boring #:
LFTP-WD
Install Date:
4/26/04

Site Name: Former Celetex Property

Site Location: Edgewater, NJ


Completion Date: 4/26/04

Geologist: Joe Krulik **Drilling Co.:** Summit

Driller: Steve Yotkovski/Ronnie Crespo **Drill Rig:** GP1100CXR

Bit: Tricone **Hammer Wt:** 140 **Drop:** 30" **Total Depth:** 14"

Sampler Type:	2" diameter SS Split Spoon	G.W. Encountered:	12'
		G.W. Stabilized:	12'



DEPTH (FT.)	SAMPLE ID AND DEPTH	PID/DIGUA (METER UNITS)	BLOWS/6.0"	RECOVERY (INCHES)	SOIL TYPE	SOIL/GEOLOGICAL DESCRIPTION	DEPTH (FT.)
1					Fill	0-2' Top Soil, Mulch	1
2		0.0			CL	2-3' Black Stained CLAY, odor, H2S detected with MiniRae.	2
3		0.0			NR	3-6' No Recovery	3
4		0.0					4
5		0.0					5
6		0.0					6
7		0.0					7
8		0.0					8
9		0.0					9
10		0.0					10
11		0.0			ML	10-12' Brown Silt, some Lt. Grey clay (Moist)	11
12		0.0					12
13		0.0			24	12-14' Same (Wet), Strong odor of H2S	13
LFTP 4-WD	0.0					Boring Terminated	14
15							15
16							16
17							17
18							18
19							19
20							20
21							21
22							22
23							23
24							24



**Environmental Waste
Management Associates, LLC**

EWMA Job #:
202334
Boring #:
LFTP-4-ED
Install Date:
4/26/04

Site Name: Former Celetex Property

Site Location: Edgewater, NJ

Completion Date: 4/26/04

Geologist: Joe Krulik

Driller: Steve Yotkovski/Ronnie Crespo

Bit: Tricone Hammer Wt: 140 Drop: 30" Total Depth: 14'

Sampler Type: 2" diameter SS Split Spoon **G.W. Encountered:** 9'

Sample Type: 2 diameter 30 split spoon G.W. Encountered: 9' G.W. Stabilized: 9'

G.W. Stabilized. 9

PT.)
ID
PPTH
DUAR
R
))
6.0"
ERY
S)
PE

SOI
RTH (1)
PEOPLE
FID/IC
ETE
UNITS
WS/W
OVE
CHE
- TV

DEPOT AMMENDMENT (MATERIAL) RECORD (INFORMATION) SHEET

BORING LOCATION SKETCH (N.T.S.)

PROPERTY BOUNDARY

LFTP-4-ND

BORING LOCATION SKETCH (N.T.S)



**Environmental Waste
Management Associates, LLC**
PO Box 5430, Parsippany, NJ, 07054
Phone: (973) 560-1400 Fax:(973) 560-0400

EWMA Job #:
202334
Boring #:
LFTP-4-V
Install Date:
4/26/04

Site Name: Former Celetex Property

Site Location: Edgewater, NJ


Completion Date: 4/26/04

Geologist: Joe Krulik **Drilling Co.:** Summit

Driller: Steve Yotkovski/Ronnie Crespo **Drill Rig:** GP1100CXR

Bit: Tricone **Hammer Wt:** 140 **Drop:** 30" **Total Depth:** 26'

Sampler Type: 2" diameter SS Split Spoon **G.W. Encountered:** 13'
G.W. Stabilized: 13'



BORING LOCATION SKETCH (N.T.S.)

DEPTH (FT.)	SAMPLE ID AND DEPTH	P/D (DIDIOU METER UNITS)	BLOWS/6.0"	RECOVERY (INCHES)	SOIL TYPE	SOIL/GEOLOGICAL DESCRIPTION		DEPTH (FT.)
1					Fill	0-2' Asphalt, Road Stone		1
2		0.0		12	CL	2-15' Lt. Grey Clay (Moist)		2
3		0.0		20				3
4		0.0		18				4
5		0.0		20				5
6		0.0		20				6
7		0.0		20				7
8		0.0		20				8
9		0.0		20				9
10		0.0		20				10
11		0.0		20				11
12		0.0		20				12
13		0.0		20				13
14		0.0		20				14
15		1.8		2"		Wet @ 13'. Slight odor		15
16						Drilled from 15-22', hard object.		16
17					NR			17
18					NR			18
19					NR			19
20								20
21								21
22								22
23				2		22-24' Brown f-GRAVEL, brick fragments (Wet)		23
24				8		24-26' Brown f-GRAVEL, trace c-sand (Wet)		24



**Environmental Waste
Management Associates, LLC**
PO Box 5430, Parsippany, NJ, 07054
Phone: (973) 560-1400 Fax:(973) 560-0400

EWMA Job #:
202334
Boring #:
LFTP-3-V
Install Date:
4/26/04

Site Name: Former Celetex Property

Site Location: Edgewater, NJ

Completion Date: 4/26/04


Geologist: Joe Krulik Drilling Co.: Summit

Driller: Steve Yotkovski/Ronnie Crespo Drill Rig: GP1100CXR

Bit: Tricone Hammer Wt: 140 Drop: 30" Total Depth: 30'

Sampler Type: 2" diameter SS Split Spoon G.W. Encountered:

G.W. Stabilized:



BORING LOCATION SKETCH (N.T.S.)

DEPTH (FT.)	SAMPLE ID AND DEPTH	PID/DIA (METER UNITS)	BLOWS/6"'	RECOVERY (INCHES)	SOIL TYPE	SOIL/GEOLOGICAL DESCRIPTION	DEPTH (FT.)
1					Fill	0-2' Red Brick (driveway), Road Stone	1
2		126					2
3		426					3
4		371					4
5		569					5
6		NR					6
7		NR					7
8		NR					8
9		NR					9
10		NR					10
11		NR					11
12		NR					12
13		NR					13
14		NR					14
15		NR					15
16		NR					16
17		NR					17
18		NR					18
19		NR					19
20		NR					20
21		NR					21
22		NR					22
23		NR					23
24		NR					24



**Environmental Waste
Management Associates, LLC**
PO Box 5430, Parsippany, NJ, 07054
Phone: (973) 560-1400 Fax:(973) 560-0400

EWMA Job #:
202334
Boring #:
LFTP-3-V
Install Date:
4/26/04

Site Name: Former Celetex Property

Site Location: Edgewater, NJ


Completion Date: 4/26/04

Geologist: Joe Krulik **Drilling Co.:** Summit

Driller: Steve Yotkovski/Ronnie Crespo **Drill Rig:** GP1100CXR

Bit: Tricone **Hammer Wt:** 140 **Drop:** 30" **Total Depth:** 30'

Sampler Type:	2" diameter SS Split Spoon			G.W. Encountered:
				G.W. Stabilized:




BORING LOCATION SKETCH (N.T.S.)

DEPTH (FT.)	SAMPLE ID AND DEPTH	PIN/PIQUA (METER UNITS)	BLOWS/6.0"	RECOVERY (INCHES)	SOIL TYPE	SOIL/GEOLOGICAL DESCRIPTION	DEPTH (FT.)
26	LFTP-3-V			2		25-27' Lt. Grey CLAY (Wet)	26
27				24	CH	27-29' Black CLAY, highly plastic, slight odor (Wet)	27
28							28
29							29
30						Boring Terminated	30
31							31
32							32
33							33
34							34
35							35
36							36
37							37
38							38
39							39
40							40
41							41
42							42
43							43
44							44
45							45
46							46
47							47
48							48
49							49



**Environmental Waste
Management Associates, LLC**
PO Box 5430, Parsippany, NJ, 07054
Phone: (973) 560-1400 Fax:(973) 560-0400

EWMA Job #:
202334
Boring #:
LFHD-1
Install Date:
4/27/04



Site Name: Former Celetex Property

Site Location: Edgewater, NJ

Completion Date: 4/27/04

Geologist: Joe Krulik Drilling Co.: Summit

Driller: Steve Yotkovski/Ronnie Crespo Drill Rig: GP1100CXR

Bit: Tricone Hammer Wt: 140 Drop: 30" Total Depth: 26'

Sampler Type: 2" diameter SS Split Spoon G.W. Encountered:

G.W. Stabilized:

DEPTH (FT.)	SAMPLE ID AND DEPTH	PID/FID/OUA (METER UNITS)	BLOWS/16.0"	RECOVERY (INCHES)	SOIL TYPE	SOIL/GEOLOGICAL DESCRIPTION	DEPTH (FT.)
1						0-24' Lt. Grey CLAY	1
2							2
3							3
4							4
5							5
6							6
7							7
8							8
9							9
10							10
11							11
12							12
13							13
14							14
15							15
16							16
17							17
18							18
19							19
20							20
21							21
22							22
23							23
24	LFHD-1			24		24-26' Black CLAY, plastic (Wet)	24



**Environmental Waste
Management Associates, LLC**
PO Box 5430, Parsippany, NJ, 07054
Phone: (973) 560-1400 Fax:(973) 560-0400

EWMA Job #:
202334
Boring #:
LFHD-2
Install Date:
4/27/04

Site Name: Former Celetex Property

Site Location: Edgewater, NJ


Completion Date: 4/27/04

Geologist: Joe Krulik Drilling Co.: Summit

Driller: Steve Yotkovski/Ronnie Crespo Drill Rig: GP1100CXR

Bit: Tricone Hammer Wt: 140 Drop: 30" Total Depth: 26'

Sampler Type: 2" diameter SS Split Spoon G.W. Encountered:
G.W. Stabilized:



BORING LOCATION SKETCH (N.T.S.)

DEPTH (FT.)	SAMPLE ID AND DEPTH	PDR/DRILL TIME (METER UNITS)	BLOWS/16.0"	RECOVERY (INCHES)	SOIL TYPE	SOIL/GEOLOGICAL DESCRIPTION		DEPTH (FT.)
1				C		0-24' Lt. Grey CLAY		1
2				U				2
3				T				3
4				T				4
5				N				5
6				G				6
7								7
8								8
9								9
10								10
11								11
12								12
13								13
14								14
15								15
16								16
17								17
18								18
19								19
20								20
21								21
22								22
23								23
24	LFHD-02 2	>1,000				24-26' Lt. Grey CLAY, (Wet) H2S 150 ppm in soil		24



**Environmental Waste
Management Associates, LLC**
PO Box 5430, Parsippany, NJ, 07054
Phone: (973) 560-1400 Fax:(973) 560-0400

EWMA Job #: 202334
Boring #: LFHD-2
Install Date: 4/27/04

Site Name: Former Celetex Property

Site Location: Edgewater, NJ

Completion Date: 4/27/04

Geologist: Joe Krulik **Drilling Co.:** Summit


Driller: Steve Yotkovski/Ronnie Crespo **Drill Rig:** GP1100CXR

Bit: Tricone **Hammer Wt:** 140 **Drop:** 30" **Total Depth:** 26"

Sampler Type: 2" diameter SS Split Spoon

G.W. Encountered:

G.W. Stabilized:



DEPTH (FT)	SAMPLE ID AND DEPTH	PINDIVIDUAL METER UNITS	BLOWS/6.0"	RECOVERY (INCHES)	SOIL TYPE	SOIL/GEOLOGICAL DESCRIPTION		DEPTH (FT)
						C	T	
1					CUTTINGS			1
2								2
3								3
4								4
5								5
6								6
7								7
8								8
9								9
10								10
11								11
12								12
13								13
14								14
15								15
16								16
17								17
18								18
19								19
20								20
21								21
22								22
23								23
24	LFHD 3					0-24' Lt. Grey CLAY		24
						24-26' Black CLAY, plastic (Moist)		



ANALYTICAL DATA REPORT


Environmental Waste Management Associates, LLC.
Lanidex Center
100 Misty Lane
Parsippany, NJ 07054

Project Name: **FORMER CELOTEX - EDGEWATER -**
202334
IAL Case Number: **E04-03710**

These data have been reviewed and accepted by:

A handwritten signature in black ink, appearing to read "Michael H. Lefun, Ph.D.", is written over a horizontal line.

Michael H. Lefun, Ph.D.
Laboratory Director



273 Franklin Road
Randolph, NJ 07869
Phone: 973 361 4252
Fax: 973 989 5288



IAL is a NELAC New Jersey Certified Lab (14751) and maintains certification in Connecticut (PH-0699), New York (11402), Rhode Island (NO-28), Florida (E92670) and in the Department of Navy IR QA Program.

Sample Summary

Case No.

E04-03710

Project Name FORMER CELOTEX - EDGEWATER - 202334

Customer EWMA - HQ

Received On 4/27/2004@19:55

Lab ID	Client Sample ID	Depth Top / Bottom	Sampling Time	Matrix	# of Cont.
03710-001	LFTP-4-ED	13 / 13.5	4/26/2004@14:00	Soil	1
03710-002	LFTP-4-ND	13 / 13.5	4/26/2004@13:15	Soil	1
03710-003	LFTP-4-WD	13 / 13.5	4/26/2004@14:40	Soil	1
03710-004	LFTP-4-V	25 / 26	4/26/2004@15:40	Soil	1
03710-005	LFTP-3-V	27 / 29	4/27/2004@11:30	Soil	1
03710-006	LFHD-1	25 / 26	4/27/2004@13:30	Soil	1
03710-007	LFHD-2	25 / 26	4/27/2004@14:00	Soil	1
03710-008	LFHD-3	25 / 26	4/27/2004@15:15	Soil	1

INTEGRATED ANALYTICAL LABORATORIES, LLC.

TABLE OF CONTENTS

	<u>Page</u>
Qualifiers	1
Conformance / NonConformance Summary	2
Laboratory Deliverables Check List	3
GC NonConformance Summary	4
Metal NonConformance Summary	5
Summary Report	6
Analytical Results	
PCBs	7
Metals	15
Methodology Summary *	
Quality Control	
PCBs	18
Method Blank Results Summary	
Standards Summary	
Surrogate Compound Recovery Results Summary	
Matrix Spike/Matrix Spike Duplicate Results Summary	
Retention Time Shift Summary	
Chromatograms	
Metals	55
Method Blank Results Summary	
Calibration Summary	
Spike Sample Results Summary	
Duplicate Sample Results Summary	
Sample Tracking	
Chains of Custody	61
Laboratory Chronicle	63

* Methodology is included in the IAL Project Information Page

INTEGRATED ANALYTICAL LABORATORIES, LLC.

MATRIX QUALIFIERS

- A - Indicates the sample is an Aqueous matrix.
- O - Indicates the sample is an Oil matrix.
- S - Indicates the sample is a Soil, Sludge or Sediment matrix.
- X - Indicates the sample is an Other matrix as indicated by Client Chain of Custody.

DATA QUALIFIERS

- B - Indicates the analyte was found in the Blank and in the sample. It indicates possible sample contamination and warns the data user to use caution when applying the results of the analyte.
- C - Common Laboratory Contaminant.
- D - The compound was reported from the Diluted analysis.
- D.F. - Dilution Factor.
- E - Estimated concentration, reported results are outside the calibrated range of the instrument.
- J - Indicates an estimated value. The compound was detected at a value below the method detection limit but greater than zero. For GC/MS procedures, the mass spectral data meets the criteria required to identify the target compound.
- MDL - Method Detection Limit.
- MI - Indicates compound concentration could not be determined due to Matrix Interferences.
- NA - Not Applicable.
- ND - Indicates the compound was analyzed for but Not Detected at the MDL.

REPORT QUALIFIERS

All solid sample analyses are reported on a dry weight basis.

All solid sample values are corrected for original sample size and percent solids.

INTEGRATED ANALYTICAL LABORATORIES, LLC.

CONFORMANCE / NONCONFORMANCE SUMMARY

Integrated Analytical Laboratories, LLC. received eight (8) soil sample(s) from Environmental Waste Management Associates, LLC. (Project: FORMER CELOTEX - EDGEWATER - 202334) on April 27, 2004 for the analysis of:

- (8) PCB
- (3) Metal - Arsenic
- (3) Metal - Lead

A review of the QA/QC measures for the analysis of the sample(s) contained in this report has been performed by:

M. Dabbs
Reviewed by

5/11/04
Date

INTEGRATED ANALYTICAL LABORATORIES, LLC.

LABORATORY DELIVERABLES CHECK LIST

Lab Case Number: E04-03710

	Check If Complete
1. Cover Page, Title Page listing Lab Certification #, facility name & address and date of report preparation.	✓
2. Table of Contents.	✓
3. Summary Sheets listing analytical results for all targeted and non-targeted compounds.	✓
4. Summary Table cross-referencing Field ID's vs. Lab ID's.	✓
5. Document bound, paginated and legible.	✓
6. Chain of Custody.	✓
7. Methodology Summary.	✓
8. Laboratory Chronicle and Holding Time Check.	✓
9. Results submitted on a dry weight basis (if applicable).	✓
10. Method Detection Limits.	✓
11. Lab certified by NJDEP for parameters or appropriate category of parameters or a member of the USEPA CLP.	✓
12. NonConformance Summary.	✓

W. D. Johnson
QC Reviewed by


5/16/04
Date

INTEGRATED ANALYTICAL LABORATORIES
CONFORMANCE/NONCONFORMANCE SUMMARY
GC ANALYSIS - PCB'S

Lab Case Number: E04 - 03710

- | | No | Yes |
|---|-------|-------|
| 1. Chromatograms Labeled/Compounds Identified (Field Samples and Method Blanks). | <hr/> | ✓ |
| 2. Standards Summary submitted. | <hr/> | ✓ |
| 3. Calibration - Initial calibration performed within 30 days before sample analysis and continuing calibration performed within 12 hrs of the sample analysis. | <hr/> | ✓ |
| 4. Blank Contamination - If yes, list compounds and concentrations in each blank: | ✓ | <hr/> |
| 5. Surrogate Recoveries meet criteria (if applicable).
If not met, list those compounds and their recoveries which fall outside the acceptable range: | <hr/> | ✓ |
| 6. Matrix Spike/Matrix Spike Duplicate meet criteria (if not, list those compounds and their recoveries/% differences which fall outside the acceptable range)
acceptable range: | <hr/> | ✓ |
| 7. Retention Time Shift Meet Criteria (if applicable). | <hr/> | ✓ |
| 8. Extraction Holding Time Met.
If not met, list number of days exceeded for each sample: | <hr/> | ✓ |
| 9. Analysis Holding Time Met.
If not met, list number of days exceeded for each sample: | <hr/> | ✓ |

Comments:


Organic Manager

05-03-04
Date

0004

INTEGRATED ANALYTICAL LABORATORIES
CONFORMANCE/NONCONFORMANCE SUMMARY
METAL ANALYSIS

Lab Case Number: E04 - 03710

	No	Yes
1. Calibration Summary Meet Criteria.		✓
2. ICP Interference Check Sample Results Meets Criteria (if applicable)		✓
3. Serial Dilution Summary Submitted (if applicable) / Meets Criteria		✓
4. Internal Standards Meet Criteria (if applicable)		✓
5. Laboratory Control Sample Summary Submitted (if applicable)/Meets Criteria		✓
6. Blank Contamination: If yes, list compounds and concentrations in each blank:		✓
7. Matrix Spike/Matrix Spike Duplicate Recoveries Meet Criteria. (If not, list those compounds and their recoveries which fall outside the acceptable range).		✓
8. Extraction Holding Time Met. If not, list number of days exceeded for each sample:		✓
9. Analysis Holding Time Met. If not, list number of days exceeded for each sample:		✓

Additional Comments:


K. Falk-Jensen
Inorganics Manager

04/30/04
Date

INTEGRATED ANALYTICAL LABORATORIES, LLC.

SUMMARY REPORT

Client: Environmental Waste Management Associates, LLC.

Project: FORMER CELOTEX - EDGEWATER - 202334

Lab Case No.: E04-03710

PARAMETER(Units)	Lab ID:	03710-001	03710-002	03710-003	03710-004		
	Client ID:	LFTP-4-ED	LFTP-4-ND	LFTP-4-WD	LFTP-4-V		
	Depth:	13/13.5	13/13.5	13/13.5	25/26		
	Matrix:	Soil	Soil	Soil	Soil		
	Sampled Date	4/26/04	4/26/04	4/26/04	4/26/04		
		Conc Q MDL	Conc Q MDL	Conc Q MDL	Conc Q MDL		
PCB's (mg/Kg-ppm)							
Aroclor-1016		ND	0.018	ND	0.017	ND	0.023
Aroclor-1221		ND	0.018	ND	0.017	ND	0.023
Aroclor-1232		ND	0.018	ND	0.017	ND	0.023
Aroclor-1242		ND	0.018	ND	0.017	ND	0.023
Aroclor-1248		ND	0.018	ND	0.017	ND	0.023
Aroclor-1254		ND	0.018	0.573	0.017	ND	0.023
Aroclor-1260		ND	0.018	ND	0.017	ND	0.023
	Lab ID:	03710-005	03710-006	03710-007	03710-008		
	Client ID:	LFTP-3-V	LFHD-1	LFHD-2	LFHD-3		
	Depth:	27/29	25/26	25/26	25/26		
	Matrix:	Soil	Soil	Soil	Soil		
	Sampled Date	4/27/04	4/27/04	4/27/04	4/27/04		
		Conc Q MDL	Conc Q MDL	Conc Q MDL	Conc Q MDL		
PCB's (mg/Kg-ppm)							
Aroclor-1016		ND	0.023	ND	0.024	ND	0.023
Aroclor-1221		ND	0.023	ND	0.024	ND	0.023
Aroclor-1232		ND	0.023	ND	0.024	ND	0.023
Aroclor-1242		ND	0.023	ND	0.024	ND	0.023
Aroclor-1248		ND	0.023	ND	0.024	ND	0.023
Aroclor-1254		ND	0.023	ND	0.024	ND	0.023
Aroclor-1260		ND	0.023	ND	0.024	ND	0.023
Metals (mg/Kg-ppm)							
Arsenic		~	~	74.5	1.58	15.3	1.54
Lead		~	~	198	0.792	18.5	0.771
						243	1.60
						268	0.799

~ = Sample not analyzed for

ND = Analyzed for but Not Detected at the MDL

0006

INTEGRATED ANALYTICAL LABORATORIES
CHAIN OF CUSTODY

CLIENT & PROJECT

Company Name: <i>EWMA-P.</i>	REPORTING
Fax to: <i>EWMA - P</i>	Fax #: _____
Address: _____	Report to: _____
Address: _____	Address: _____
Telephone #: _____	Invoice to: <i>EWMA - P</i>
Fax #: _____	Address: _____
Project Name: <i>Former Celotex-Edgewater</i>	Address: _____
Project Manager: <i>P. Schatz</i>	Address: _____
Reference ID#: <i>202334</i> PO#: <i>6422</i>	Address: _____

SAMPLE INFORMATION

Sampling							
Sample ID	Sample Description	Date	Time	am pm	Matrix	# of Containers	Lab ID
LFTP-4-ED	13-13.5	4/26/9	1400	X	SL	1	1
LFTP-4-ND	13-13.5	/	1315	X		1	2
LFTP-4-WD	13-13.5	/	1440	X		1	3
LFTP-4-V	25-26	/	1540	X		1	4
LFTP-3-V	27-29	4/27/9	1130	X		1	5
LFID-1	25-26	1	1330	X		1	6
LFID-2	25-26	1	1420	X		1	7
LFID-3	25-26	1	1515	X	GW	8	8

Please print legibly and fill out completely. Samples cannot be processed and the turnaround time will not start until any ambiguities have been resolved.

Concentrations Expected

Known Hazard: yes no

LOW MED HIGH

Describe:

CUSTODY LOG

Signature	Date	Time	Signature
Relinquished by: <i>J. S. Kelt</i>	4/27/9	1625	Received by: <i>J. S. Kelt</i>
Relinquished by: <i>J. S. Kelt</i>	4/27/9	1855	Received by: <i>J. S. Kelt</i>
Relinquished by: <i>J. S. Kelt</i>			Received by: <i>J. S. Kelt</i>
Relinquished by: <i>J. S. Kelt</i>			Received by: <i>J. S. Kelt</i>
Relinquished by: <i>J. S. Kelt</i>			Received by: <i>J. S. Kelt</i>

Comments: * High H2S in samples

Lab Case #

3710

PAGE: / OF /

PROJECT INFORMATION



E 0 4 - 0 3 7 1 0

Case No. E04-03710

Project FORMER CELOTEX - EDGEWATER - 202334

Customer	EWMA - HQ	P.O. #	L6422
Contact	Paul Schatz	Received	4/27/2004 19:55
EMail	Paul.Schatz@ewma.com	Verbal Due	5/12/2004
Phone	(973) 560-1400	Fax	1(973) 560-0400
Report To		Bill To	
Lanidex Center 100 Misty Lane Parsippany, NJ 07054 Attn: Paul Schatz		Lanidex Center 100 Misty Lane Parsippany, NJ 07054 Attn: Paul Schatz	
Report Format Reduced			
Additional Info <input type="checkbox"/> State Form <input type="checkbox"/> Field Sampling <input type="checkbox"/> Conditional VOA			

<u>Lab ID</u>	<u>Client Sample ID</u>	<u>Depth Top / Bottom</u>	<u>Sampling Time</u>	<u>Matrix</u>	<u>Unit</u>	<u># of Containers</u>
03710-001	LFTP-4-ED	13 / 13.5	4/26/2004 @ 14:00	Soil	mg/Kg	1
03710-002	LFTP-4-ND	13 / 13.5	4/26/2004 @ 13:15	Soil	mg/Kg	1
03710-003	LFTP-4-WD	13 / 13.5	4/26/2004 @ 14:40	Soil	mg/Kg	1
03710-004	LFTP-4-V	25 / 26	4/26/2004 @ 15:40	Soil	mg/Kg	1
03710-005	LFTP-3-V	27 / 29	4/27/2004 @ 11:30	Soil	mg/Kg	1
03710-006	LFHD-1	25 / 26	4/27/2004 @ 13:30	Soil	mg/Kg	1
03710-007	LFHD-2	25 / 26	4/27/2004 @ 14:00	Soil	mg/Kg	1
03710-008	LFHD-3	25 / 26	4/27/2004 @ 15:15	Soil	mg/Kg	1

<u>Sample #</u>	<u>Tests</u>	<u>Status</u>	<u>QA Method</u>
001 PCB		In Process	8082
002 PCB		In Process	8082
003 PCB		In Process	8082
004 PCB		In Process	8082
005 PCB		In Process	8082
006 PCB	" Arsenic - As	In Process	6020
	" Lead - Pb	In Process	6020
007 PCB		In Process	8082
	" Arsenic - As	In Process	6020
	" Lead - Pb	In Process	6020
008 PCB		In Process	8082
	" Arsenic - As	In Process	6020
	" Lead - Pb	In Process	6020

04/28/2004 15:39 by Gina - NOTE 1

SAMPLES MAY CONTAIN HIGH LEVELS OF H2S.

INTEGRATED ANALYTICAL LABORATORIES, LLC

SAMPLE RECEIPT VERIFICATION

CASE NC **E04****03710**

CLIENT:

RUMA

COOLER TEMPERATURE: 2° - 6°C: (See Chain of Custody)

CHAIN OF CUSTODY: COMPLETE / INCOMPLETE Comments: _____

Sample Bottles Intact: Comments: _____Sample Labels Intact/ Correct: _____Sufficient Sample Volume: _____Correct bottles/ preservative: _____Samples received in holding time/ prep time: _____Headspace/ bubbles in voa samples: _____Samples to be subcontracted: _____Preserved Sample pH checked: _____

(Excluding voa samples) _____

KEY

- | | |
|---|-------|
| ✓ | = YES |
| ✗ | = NO |
| Ⓐ | = N/A |

ADDITIONAL COMMENTS: _____
_____SAMPLE(S) VERIFIED BY: INITIAL **MR** DATE **1/22/04**CORRECTIVE ACTION REQUIRED: YES (SEE BELOW) NO CLIENT NOTIFIED: YES Date/ Time: _____ NO

PROJECT CONTACT: _____

SUBCONTRACTED LAB: _____

DATE SHIPPED: _____

ADDITIONAL COMMENTS: _____

VERIFIED/TAKEN BY: INITIAL **AP** DATE _____

LABORATORY CUSTODY CHRONICLE

Case No. **E04-03710**

Client EWMA - HQ





Project FORMER CELOTEX - EDGEWATER - 202334

Department:	PCB	03710-001	Soil	Preparation	Analyst	Analysis	Analyst
				Date / Time		Date / Time	
GC		-002	Soil		Eleanor	4/28/04	Maggie
"		-003	Soil		Eleanor	4/28/04	Maggie
"		-004	Soil		Eleanor	4/28/04	Maggie
"		-005	Soil		Eleanor	4/28/04	Maggie
"		-006	Soil		Eleanor	4/28/04	Maggie
"		-007	Soil		Eleanor	4/28/04	Maggie
"		-008	Soil		Eleanor	4/28/04	Maggie
Department: Metals							
Arsenic - As		03710-006	Soil	4/28/04	Lisa	4/29/04	Helge
"		-007	Soil	4/28/04	Lisa	4/29/04	Helge
"		-008	Soil	4/28/04	Lisa	4/29/04	Helge
Lead / Pb		03710-006	Soil	4/28/04	Lisa	4/29/04	Helge
"		-007	Soil	4/28/04	Lisa	4/29/04	Helge
"		-008	Soil	4/28/04	Lisa	4/29/04	Helge


Review and Approval: MC/DRS 5/11/04

SRID: NJD981876642
Desc: Subsurface Soil
IAI Case# E04-03710
EWMA# 202334 Edgewake
Submit Date 8/18/04


**GYPSUM LANDFILL COVER
SOIL BORING PHOTO LOGS**
June 7 and 22, 2004




LEGEND




**GYPSUM LANDFILL COVER
SOIL BORING PHOTO LOGS**
June 7 and 22, 2004




LEGEND







**GYPSUM LANDFILL COVER
SOIL BORING PHOTO LOGS**
June 7 and 22, 2004




LEGEND




**GYPSUM LANDFILL COVER
SOIL BORING PHOTO LOGS**
June 7 and 22, 2004




LEGEND







**GYPSUM LANDFILL COVER
SOIL BORING PHOTO LOGS**
June 7 and 22, 2004




LEGEND

	Asphalt
	Gravel Base
	Top Soil
	Brick Paver
	Fill
	Gypsum


**GYPSUM LANDFILL COVER
SOIL BORING PHOTO LOGS**
June 7 and 22, 2004



LEGEND




**GYPSUM LANDFILL COVER
SOIL BORING PHOTO LOGS**
June 7 and 22, 2004




LEGEND

	Asphalt
	Gravel Base
	Top Soil
	Brick Paver
	Fill
	Gypsum





**GYPSUM LANDFILL COVER
SOIL BORING PHOTO LOGS**
June 7 and 22, 2004



LEGEND




**GYPSUM LANDFILL COVER
SOIL BORING PHOTO LOGS**
June 7 and 22, 2004



LEGEND

	Asphalt
	Gravel Base
	Top Soil
	Brick Paver
	Fill
	Gypsum





**GYPSUM LANDFILL COVER
SOIL BORING PHOTO LOGS**
June 7 and 22, 2004



LEGEND

	Asphalt
	Gravel Base
	Top Soil
	Brick Paver
	Fill
	Gypsum


**GYPSUM LANDFILL COVER
SOIL BORING PHOTO LOGS**
June 7 and 22, 2004



LEGEND

	Asphalt
	Gravel Base
	Top Soil
	Brick Paver
	Fill
	Gypsum

**GYPSUM LANDFILL COVER
SOIL BORING PHOTO LOGS**
June 7 and 22, 2004




LEGEND

	Asphalt
	Gravel Base
	Top Soil
	Brick Paver
	Fill
	Gypsum


GYPSUM LANDFILL COVER

SOIL BORING PHOTO LOGS


June 7 and 22, 2004




LEGEND



**GYPSUM LANDFILL COVER
SOIL BORING PHOTO LOGS**
June 7 and 22, 2004




LEGEND




GYPSUM LANDFILL COVER

SOIL BORING PHOTO LOGS

June 7 and 22, 2004




LEGEND



- Asphalt
- Gravel Base
- Top Soil
- Brick Paver
- Fill
- Gypsum


**GYPSUM LANDFILL COVER
SOIL BORING PHOTO LOGS**
June 7 and 22, 2004



LEGEND

	Asphalt
	Gravel Base
	Top Soil
	Brick Paver
	Fill
	Gypsum


**GYPSUM LANDFILL COVER
SOIL BORING PHOTO LOGS**
June 7 and 22, 2004






LEGEND

	Asphalt
	Gravel Base
	Top Soil
	Brick Paver
	Fill
	Gypsum

**GYPSUM LANDFILL COVER
SOIL BORING PHOTO LOGS**
June 7 and 22, 2004



LEGEND

	Asphalt
	Gravel Base
	Top Soil
	Brick Paver
	Fill
	Gypsum